384

CHITALDROOG DIVISION.

ADVERTISEMENT.

The 19th September 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldroog Division, up to 10th October 1887, for restoring Chikyammaganur Tank, Registered No. 174 of Holalkere Taluk, sanctioned for Rs. 8,980. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldroog between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring Chikyammaganur Tank, Registered No. 174," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of Estimate for restoring Chikyammaganur Tank, No. 174, Holalkere Taluk.

Description of Work.		Unit of Work.	Rate per Unit.
Bund.			
Earthwork to bund	19,836	C. Yd.	
Do breach	10,566	do	
Excavating and removing silt	315	do	
Rough stone, old	1,023	do	
Do new	3,986	do	
Grade stones, No.	42	Each.	
B. M. do	2	do	
Tank No. stone	1	do	
Left kodi	(160')	..	
Earthwork	38	C. Yd.	
Brick in chunam	954	C. Ft.	
Stone in do	936	do	
Slab stones	645	S. Ft.	
Rough stone apron	440	C. Yd.	
Sluice.			
Ordinary design No. 2 in lump			

J. B. CHALON,
Offg. Executive Engineer.

TUMKUR DIVISION.

ADVERTISEMENT.

The 19th September 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 10th October 1887, for restoring the Chikkachangavi Tank, Registered No. 213,

Gubbi Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1888.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Tumkur between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the Chikkachangavi Tank", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantity of work to be done on Chikkachangavi Tank :—

Items of Work.	Per	Quantity.	Rate.	Cost.	Total of each.	Grand Total.
Bund.—						
Earthwork	C. Yd.	5,469				
Do	,,	19,473				
New stone work	,,	885				
Cutting trees	L. S.	Rs. 50				
Clearing silt & baling water ..	Do	Rs. 100				
Grade stones	E.	42				
B. M. stones	E.	2				
Sluice No. I.—						
Earthwork excavation ..	C. Yd.	275				
Brick in surki mortar ..	C. Ft.	676				
Plastering with do ..	Sq.	5·00				
Slab stones	S. Ft.	153				
New stone work	C. Yd.	41				
Sluice No. II.—						
Earth excavation	L. S.	Rs. 15				
Brick in surki mortar ..	C. Ft.	712				
Plastering with do ..	Sq.	400				
Stone slabs	S. Ft.	154				
Left Wasteweir.—						
Earth excavation	C. Yd.	6,413				
Brick in surki mortar ..	C. Ft.	1,934				
Plastering with do	Sq.	500				
Stone slabs	S. Ft.	245				
New stone work ..	C. Yd.	648				
Cutting rock, &c.	L. S.	Rs. 100				
Right Wasteweir.—						
Excavation	C. Yd.	1,792				
Brick in surki	C. Ft.	2,245				
Plastering with do ..	Sq.	10·00				
Levelling old body wall ..	L. S.	Rs. 10				
New stone work	C. Yd.	394				
Old stone work	Do	495				
Stone slabs	C. Ft.	1,052				

C. T. DALAL,
Executive Engineer.